


CONCRETE PARKING BUMPERS
REQUIRED IF BARRIER CURB
IS NOT PRESENT

RESERVED HANDICAP PARKING SIGN



STRIPING & SYMBOL
PER IL ACCESSIBILITY
CODE

Total Off-Street
Parking Spaces
Provided

Number of
Accessible Parking
Spaces Required

| | | |
|--------------|-------|---|
| 1 to 25 | | 1 |
| 26 to 50 | | 2 |
| 51 to 75 | | 3 |
| 76 to 100 | | 4 |
| 101 to 150 | | 5 |
| 151 to 200 | | 6 |
| 201 to 300 | | 7 |
| 301 to 400 | | 8 |
| 401 to 500 | | 9 |
| 501 to 1,000 | | 2% of total |
| over 1,000 | | 20 plus 1 for each 100 over 1,000 |

NOTES:

1. ADA SIGNAGE SHALL BE R7-8 STANDARD WITH R7-1101 \$250 FINE SIGN, SHALL HAVE A SIGN HEIGHT OF 5', AND MUST BE WITHIN 5' OF THE FRONT OF THE PARKING STALL
2. MAX SLOPE SHALL BE 2% IN ANY DIRECTION
3. REFER TO CURRENT EDITION OF THE ILLINOIS ACCESSIBILITY CODE, SECTION 400.310(c) AND ILLUSTRATIONS "B" (FIGURE 9), "C" AND "D"
4. ACCESSIBLE PARKING MUST BE LOCATED ON THE SHORTEST ACCESSIBLE ROUTE TO AN ACCESSIBLE ENTRANCE.

VILLAGE OF ELK GROVE VILLAGE

ADA PARKING STALL (TYPICAL)

